

**ITEM 602.3554 09 - LINING 1350 MM PIPE WITH POLYESTER FORMED IN PLACE
PIPE LINER**

DESCRIPTION

This work shall consist of Lining a 1350 mm Pipe with Polyester Formed in Place Pipe Liner in accordance with the contract documents and as directed by the Engineer. All provisions of Standard Specification Section 602 pertaining to Lining with Polyester Formed in Place Pipe Liner shall apply.

MATERIALS

Material requirements are specified in subsection 706-06 of the 2006 Standard Specifications.

CONSTRUCTION DETAILS

Provide the Engineer with written details of how the work is to be progressed a minimum of 10 days prior to starting. Include pipe manufacturer's instructions, dewatering, assembly drawings, necessary insertion and bracing methods, and proposed shotcreting, concrete, and void filling methods.

METHOD OF MEASUREMENT

This work will be measured as the number of meters along the bottom centerline, measured to the nearest meter of Lining with Polyester Formed in Place Pipe Liner satisfactorily installed.

BASIS OF PAYMENT

The unit price bid shall include the cost of furnishing all labor, materials, and equipment necessary to satisfactorily complete the work.