

**ITEM 63603.6001XX M - INSTALLATION OF REINFORCED CONCRETE PIPE,
EMERGENCY STANDBY CONTRACT WORK**

DESCRIPTION. The work shall consist of installing reinforced concrete pipe for drainage in accordance with this specification, the contract plans.

MATERIALS. Materials requirements are specified in subsection 706-02, 706-03 &706-07.

CONSTRUCTION DETAILS. Apply the requirements specified in Section 603-3.

METHOD OF MEASUREMENT. This work shall be measured as the number of meters of pipe installed. Measurement shall be made along the bottom center of the pipe.

BASIS OF PAYMENT. The cost of furnishing the reinforced concrete pipe will be paid for separately under their respective contract items.

End sections, excavation, granular fill and backfill will be paid for separately under their respective items.

The requirements of Subsection 603-5.01 shall apply.

Payment will be made under:

<u>ITEM NO.</u>	<u>ITEM DESCRIPTION</u>	<u>PAY UNIT</u>
63603.600101M	Installation of Reinforced Concrete Pipe, 450 mm - 675 mm Diameter, Emergency Standby Contract Work	Meter
63603.600102M	Installation of Reinforced Concrete Pipe, 750 mm - 900 mm Diameter, Emergency Standby Contract Work	Meter
63603.600103M	Installation of Reinforced Concrete Pipe, 1050 mm - 1200 mm Diameter, Emergency Standby Contract Work	Meter