

ITEM 603.6101NN63 - CORRUGATED STEEL, CORRUGATED ALUMINUM OR SMOOTH INTERIOR CORRUGATED POLYETHYLENE CULVERT AND STORM DRAIN PIPE – INSTALL ONLY, EMERGENCY STANDBY CONTRACT WORK

DESCRIPTION

The work shall consist of installing corrugated steel, corrugated aluminum or smooth interior corrugated polyethylene pipe for drainage in accordance with this specification, the contract plans and the Standard Sheet titled “Installation Details For Corrugated Metal and Structural Plate Pipe and Pipe-Arches”.

MATERIALS

None specified.

CONSTRUCTION DETAILS

Apply the requirements specified in Section 603-3.

METHOD OF MEASUREMENT

This work will be measured as the number of meters of pipe installed. Measurement will be made along the bottom center of the pipe.

BASIS OF PAYMENT

The unit price bid shall include the cost of all labor and equipment necessary to install the pipe satisfactorily.

The cost of furnishing the pipe will be paid for separately under the respective contract items.

End sections, excavation, granular fill and backfill will be paid for separately under their respective contract items.

The requirements of Subsection 603-5.01 shall apply.

Payment will be made under:

<u>ITEM NO.</u>	<u>ITEM DESCRIPTION</u>	<u>PAY UNIT</u>
603.61010163	Corrugated steel, corrugated aluminum or Smooth Interior Corrugated Polyethylene Culvert and Storm Drain Pipe, 450 mm - 600 mm Diameter – Install Only, Emergency Standby Contract Work	Meter
603.61010263	Corrugated steel, corrugated aluminum or Smooth Interior Corrugated Polyethylene Culvert and Storm Drain Pipe, 750 mm - 900 mm Diameter – Install Only, Emergency Standby Contract Work	Meter
603.61010363	Corrugated steel, corrugated aluminum or Smooth Interior Corrugated Polyethylene Culvert and Storm Drain Pipe, 1050 mm - 1200 mm Diameter – Install Only, Emergency Standby Contract Work	Meter