

ITEM 603.9910XX06 - INTERIM STORM DRAINS

DESCRIPTION

This work shall consist of furnishing, installing, maintaining, and removing INTERIM STORM DRAINS in accordance with the contract documents and as directed by the Engineer.

MATERIALS

All the provisions of Section 603-2.01 shall apply except as modified herein. Material may be in used condition but must be acceptable to the Engineer.

CONSTRUCTION DETAILS

The Contractor shall install the interim storm drains in accordance with the contract documents. All the Provisions of Section 603-3 shall apply except as modified herein.

Excavation and backfill shall be in conformance with the Construction Details of Section 206-3

METHOD OF MEASUREMENT

This work will be measured on a lump sum basis.

BASIS OF PAYMENT

The lump sum price bid shall include the cost of furnishing all labor, materials, and equipment, including excavation and backfill, necessary to satisfactorily complete the work.

Payment shall be made under Item 603.9910XX06 where XX represents the location of the installation as serialized in the Contract Documents.

Payment will be made at the lump sum bid price for each Interim Storm Drain as follows:

Seventy-five (75) percent when the Interim Storm Drain is complete and functional.

Twenty-five (25) percent when the Interim Storm Drain is permanently removed.