

**ITEM 603.9945 05 - SUMP PUMP AND GUTTER DRAIN OUTLET TO STORM
SEWER**

DESCRIPTION:

This work shall consist of furnishing and installing polyvinyl chloride pipe and concrete block for drainage in accordance with this specification and in conformity with the lines, grades and sections shown in the contract documents.

MATERIALS:

The polyvinyl chloride pipe, fittings and solvent content shall conform to the requirements of 706-15, PVC Plastic Drain Pipe System.

The concrete block shall conform to the requirements of 704-04, Concrete Block (Slope Paving).

CONSTRUCTION DETAILS:

The following provisions of Section 603 – Culverts and Storm drains shall apply for the installation of the pipe:

- 603-3.01 Excavation. Side limits to be measured from the exterior walls.
- 603-3.02 A & B Laying Pipe. General & Handling and assembly of pipe.
- 606-3.03 Bedding and Backfilling Pipe
- 606-3.04A Damaged Pipe and Repair. General

METHOD OF MEASUREMENT:

This work will be measured as the number of meters of pipe installed. Measurements will be made along the bottom center line of the horizontal section of pipe installed. No additional measurement will be made for the riser.

BASIS OF PAYMENT:

The unit price bid per meter shall include the cost of furnishing all labor, materials and equipment necessary to satisfactorily complete the work, including all excavation, pipe, pipe fittings, riser, solvent cement, concrete blocks and backfilling.