

ITEM 10604.0722 M - RESETTING EXISTING DRAINAGE FRAMES ON NEW DRAINAGE STRUCTURES

DESCRIPTION

This work shall consist of removing and storing existing drainage frames, complete with grates, covers, and appurtenances and resetting to grade on new drainage structures.

MATERIALS

None Specified.

CONSTRUCTION DETAILS

The existing frames, grates, covers, and appurtenances shall be removed, stored if necessary, cleaned and reset to the line and grade indicated in the plans or as directed by the Engineer.

METHOD OF MEASUREMENT

This work will be measured by the number of existing drainage frames, complete with grates, covers, and appurtenances, reset to grade on new drainage structures.

BASIS OF PAYMENT

The unit price bid for resetting each drainage frame shall include the cost of all labor and equipment necessary to complete the work.

Any frames, grates, covers, and appurtenances broken through carelessness on the part of the contractor shall be replaced at the contractor's expense.