

ITEM 63606.10XXM - BOX BEAM GUIDE RAILING, EMERGENCY STANDBY CONTRACT WORK

All the provisions of Section 606 with respect to Box Beam Guide Railing apply except:

1. Supply galvanized or rustic tangent sections or, galvanized or rustic shop curved sections of box beam guide railing as stated in the initial order or as directed by the Engineer.
2. Payment for guide rail under this item shall include the unit price bid and the measured quantity multiplied by the payment factor for various typical post spacings listed in Table 606-2 of the Standard Specifications and the appropriate payment factor for the different types of box beam guide rail listed in Table 63606-2.

TABLE 63606-2

PAYMENT FACTORS FOR DIFFERENT TYPES OF BOX BEAM GUIDE RAIL

GUIDE RAIL TYPE	PAYMENT FACTOR
Galvanized Box Beam	1.00
Galvanized Box Beam (Shop Curved)	1.10
Rustic Box Beam	1.10
Rustic Box Beam (Shop Curved)	1.15

Payment = (Bid Price) x (Measured Quantity) x (Factor from Table 606-2) x (Factor from Table 63606-2).

Payment will be made under:

<u>ITEM NO.</u>	<u>ITEM DESCRIPTION</u>	<u>PAY UNIT</u>
63606.1001M	Box Beam Guide Railing, Emergency Standby Contract Work, Quantity Range 1 (0 to 29.9)	m
63606.1002M	Box Beam Guide Railing, Emergency Standby Contract Work, Quantity Range 2 (30 to 149.9)	m
63606.1003M	Box Beam Guide Railing, Emergency Standby Contract Work, Quantity Range 3 (150 or Greater)	m

ITEM 63606.10XXM - BOX BEAM GUIDE RAILING, EMERGENCY STANDBY
CONTRACT WORK