

**ITEM 10606.3299 M - BACK UP POSTS FOR HALF SECTION CONCRETE
BARRIER**

Reason for DisApproval:

The work and payment for backup posts is already included in the Standard Specification items.

This specification is
DisApproved

ITEM 10606.3299 M - BACK UP POSTS FOR HALF SECTION CONCRETE BARRIER

DESCRIPTION:

The contractor shall furnish and place galvanized back up posts for concrete half section, in accordance with the plans, specifications, and as ordered by the Engineer.

MATERIALS:

The steel back up posts shall be W150 x 14 shapes. They shall conform to ASTM A36.

Galvanizing shall be in accordance with Materials Specification 719.01, "Galvanized Coatings and Repair Methods," Type 1, of the Standard Specifications.

CONSTRUCTION DETAILS:

Back up posts shall be erected in the position and manner indicated on the plans and as ordered by the Engineer.

Posts shall be driven unless otherwise ordered by the Engineer. The driving shall be accomplished with approved methods and equipment that will leave the posts in their final position, free of any distortion, burring, or other damage.

METHOD OF MEASUREMENT:

This work will be measured by the number of back up posts erected in accordance with the plans, specifications, or as directed by the Engineer.

BASIS OF PAYMENT:

The unit price bid per each back up post shall include the cost of all labor, materials, and equipment, including galvanizing necessary to satisfactorily complete the work.