

**ITEM 15606.3802 M - REMOVAL OF FREE STANDING PRECAST  
CONCRETE MEDIAN  
BARRIER**

**DESCRIPTION.** The Contractor shall remove free standing precast concrete median barrier installed by others where indicated on the plans or where directed by the Engineer.

**MATERIALS.** Not specified.

**CONSTRUCTION DETAILS.** The Contractor shall disassemble and remove free standing precast concrete median barrier where indicated on the plans or directed by the Engineer. All free standing precast concrete median barrier removed under this item shall become the property of the Contractor and be removed from the Contract. Removed barrier sections, free from unrepairable damage and/or defect to concrete and/or connection which would adversely affect their performance, may be used as Temporary Concrete Median Barrier.

**METHOD OF MEASUREMENT.** Removal of free standing precast concrete median barrier will be measured by the number of meters of barrier to be removed shown on the plans or the number of meters of barrier directed to be removed by the Engineer. Measurement shall be made by multiplying the number of units removed by 6 meters.

**BASIS OF PAYMENT.** The unit price per meter shall include all material, equipment and labor necessary to remove the barrier.