

**ITEM 606.50 06 - DECORATIVE TIMBER BARRIER**

**DESCRIPTION**

Under this item the contractor shall furnish and erect wood timber barriers in accordance with the plans, specifications and as ordered by the Engineer.

**MATERIALS**

The timber posts and rails shall be pressure treated lumber of the size shown on the plans and conform to material specifications of § 712-13.

The posts and rails shall be treated with wood preservative conforming to § 708.31, Wood Preservative - Water Borne.

Fittings & Fasteners shall conform to the material requirements of § 719.01, Galvanized Coatings and Repair Methods, Type 2.

**CONSTRUCTION DETAILS**

The timber barriers shall be erected as shown on the plans or as directed by the Engineer true to line and grade on a firmly tamped base. The space around them shall be backfilled and tamped in 150 mm layers. The rails shall be attached as shown on the plans.

After erection of the timber barriers, one coat of brown stain as approved by the Engineer shall be applied to the posts and rails.

**METHOD OF MEASUREMENT**

This work will be measured by the actual number of linear meters erected in accordance with the contract documents.

**BASIS OF PAYMENT**

The unit price bid per linear meter shall include the cost of furnishing all labor, materials and equipment necessary to complete the work including the excavation and backfill.