

**ITEM 08606.5101 M - RESETTING CORRUGATED BEAM GUIDE RAILING  
IN PLACE**

**ITEM 08606.5301 M - RESETTING BOX BEAM GUIDE RAILING IN PLACE**

**ITEM 08606.590201 M - RESETTING BOX BEAM GUIDE RAILING END  
ASSEMBLY IN PLACE**

All requirements of Section 606 of the Standard Specifications, relating to resetting guide rail shall apply except:

Under "Construction Details" section 606-3.06 and 606-3.12, the contractor shall not remove, store or clean the existing railing or posts. The work shall be done in place, without removing the guide rail. The reset railing shall be set to the proper height and alignment as determined by the Engineer.

Under "Basis of Payment", the following progress payment percentages will be used:

1. 85% of the unit price bid of the quantity of guide rail lifted and reset, including tamping the existing ground around the posts which are to remain in place.
2. 15% of the unit price bid of the quantity to backfill the voids around the posts, including other disturbed areas caused by these operations, and graded to the satisfaction of the Engineer.