

ITEM 606.66-----02M - REMOVE AND STORE MEDIAN BARRIER END ASSEMBLIES

DESCRIPTION

Under this item, the Contractor shall remove existing median barrier end assemblies from the locations shown on the plans or indicated by the Engineer. All usable components shall be stored on-site at locations approved by the Engineer or off-site at locations designated in the Contract Documents.

Any unusable components shall become the property of the Contractor and shall be disposed of properly by the Contractor.

MATERIALS

None Specified.

CONSTRUCTION DETAILS

The Contractor shall remove designated existing median barrier end assemblies, including any below grade parts and transitions, and neatly store the component parts in separate piles at locations designated for future pick up by Department forces, or its designee. The work shall be done so as to salvage all usable parts. Unusable material shall be disposed of by the Contractor. Any excavations done shall be backfilled with suitable material so as to match the surrounding area.

METHOD OF MEASUREMENT

This work will be measured by the number of End Assemblies properly removed and stored at locations approved by the Engineer or designated in the Contract Documents.

BASIS OF PAYMENT

The unit price bid for each of these items shall include the cost of furnishing all labor, equipment and material necessary to complete the work, including excavation and backfill.