

ITEM 15606.70 M - REMOVE AND DISPOSE OF CABLE GUIDE RAIL AND STORE POSTS

ITEM 15606.71 M - REMOVE AND DISPOSE OF CORRUGATED BEAM GUIDE

RAIL AND STORE POSTS

ITEM 15606.72 M - REMOVE AND DISPOSE OF CORRUGATED BEAM MEDIAN BARRIER AND STORE POSTS

ITEM 15606.73 M - REMOVE AND DISPOSE OF BOX BEAM GUIDE RAIL AND

MEDIAN BARRIER AND STORE POSTS

DESCRIPTION. Under these items, the Contractor shall remove existing guide rail or median barrier from the locations shown on the plans or indicated by the Engineer. Usable posts, usable fasteners designated in the Contract Documents and usable hardware designated in the Contract Documents shall be stored on-site at locations approved by the Engineer or off-site at locations designated in the Contract Documents. Guide rail or median barrier elements, other than the above, shall become the property of the Contractor and shall be disposed of offsite by the Contractor.

MATERIALS. Pallets shall be strongly constructed of substantial, sound, weather-resistant materials. Pallets may be new or used. Pallets shall be subject to the approval of the Engineer. Containers, cloth bags, and pavement repair materials shall be subject to approval by the Engineer.

CONSTRUCTION DETAILS. All usable posts and such usable hardware and usable fasteners as are designated in the Contract Documents to be stored shall be neatly stored by the Contractor on-site at locations designated or approved by the Engineer or, when designated in the contract documents, at offsite locations designated in the Contract Documents. The removal and storage work shall be done with reasonable care in a manner so as to not damage material designated for storage. Posts shall be neatly stacked on and secured to pallets with a maximum of fifty posts per pallet. Posts from the different type barriers shall be stored on separate pallets. Hardware items and fasteners designated for storage shall be stored separately, by type, in clean labeled weather proof containers or in labeled cloth bags. Pallets, containers, and cloth bags shall become the property of the State.

Support bolts in the 75 mm posts of corrugated barriers shall remain in the posts. Rail support plates used with box beam median barrier shall be detached from the post and be stored together in containers or bags along with their fasteners.

Bituminous surfaces, except those to be removed, shall be repaired to a safe and satisfactory condition to the satisfaction of the Engineer.

METHOD OF MEASUREMENT. The quantity to be measured for payment will be the number of linear meters of guide rail or median barrier removed in accordance with these specifications and the direction of the Engineer. Payment factors will not apply to this work.

BASIS OF PAYMENT. The unit price bid per for this work shall include the cost of furnishing all labor, equipment and materials necessary to complete the work. The work will be eligible for progress payments in accordance with the following: 75% upon satisfactory completion of all necessary removal, disposal, and storage; 25% upon satisfactory filling the resulting voids and restoring the affected areas to the satisfaction of the Engineer.