

ITEM 10606.7010 M - REMOVING AND STORING WOOD FACED CABLE GUIDE

RAILING AND MEDIAN BARRIER

ITEM 10606.7011 M - REMOVING AND DISPOSING ANCHORAGE UNITS FOR WOOD FACED CABLE GUIDE RAILING AND MEDIAN BARRIER

DESCRIPTION

This work shall consist of the removal and storage of wood faced cable guide railing and/or median barrier, and the removal and disposal of concrete anchorage units for wood faced cable guide railing and/or median barrier at the locations shown in the plans and where directed by the Engineer.

MATERIALS

Not specified.

CONSTRUCTION DETAILS

General.

Proper precautions shall be taken to protect traffic at all times.

The surface in the areas where the guide railing, median barrier, and anchorage units are removed shall be restored by the Contractor to match, as nearly as possible, the adjacent surfaces. This may require sodding, seeding and mulching, paving, or other treatment as directed by the Engineer. Seed shall be NK100 Perennial Rye grass unless otherwise directed by the Engineer.

Removing and Storing Wood Faced Cable Guide Railing and Median Barrier.

The Contractor shall remove the existing wood faced cable guide railing, and/or median barrier, and neatly stack its component parts in separate piles at locations designated by the Engineer for future pick up by Department forces, or its designee. The work shall be done in a workmanlike manner so as to salvage all usable parts. Any usable parts damaged through carelessness on the part of the Contractor shall be replaced by the Contractor. Unusable material shall be disposed of by the Contractor off the work site.

Post holes shall be backfilled with a suitable material and compacted in a manner approved by the Engineer.

Removing and Disposing Anchorage Units for Wood Faced Cable Guide Railing and Median Barrier.

The Contractor shall remove the existing anchorage units and dispose of them off the work site.

Excavation and backfill shall be in conformance with the requirements of Sub-section 206-3.01 and 206-3.03 of the Standard Specifications.

METHOD OF MEASUREMENT

Removing and Storing Wood Faced Cable Guide Railing and Median Barrier.

This work will be measured by the number of meters of wood faced cable guide railing and/or median barrier removed, measured center to center of end posts.

ITEM 10606.7010 M - REMOVING AND STORING WOOD FACED CABLE GUIDE

RAILING AND MEDIAN BARRIER

ITEM 10606.7011 M - REMOVING AND DISPOSING ANCHORAGE UNITS FOR WOOD FACED CABLE GUIDE RAILING AND MEDIAN BARRIER

Removing and disposing Anchorage Units for Wood Faced Cable Guide Railing and Median Barrier.

This work will be measured by the number of anchorage units for wood faced cable guide railing and/or median barrier removed and disposed of. The anchorage units shall consist of the concrete anchor and all associated hardware, cable, and wood facing connecting the concrete anchor to the guide railing or median barrier.

BASIS OF PAYMENT

The unit price bid for each item shall include the cost of all labor, materials, and equipment necessary to complete the work including excavation and backfill, restoration of disturbed areas, and the replacement of any material damaged due to the Contractor's operations.

Progress payments will be made as follows:

Removing and Storing Wood Faced Cable Guide Railing and Median Barrier.

Payment will be made for 75% of the quantity of guide railing and/or median barrier removed when the guide railing and/or median barrier is removed and stored as specified. The remaining 25% will be paid when the voids have been backfilled and disturbed areas satisfactorily restored.

Removing and Disposing Anchorage Units for Wood Faced Cable Guide Railing and Median Barrier.

Payment will be made for 75% of the unit price bid for each anchorage unit when the anchorage unit is removed and disposed of as specified. The remaining 25% will be paid when the voids have been backfilled and disturbed areas satisfactorily restored.