

ITEM 03606.88 M - RESETTING PIER PROTECTION

DESCRIPTION:

This work shall consist of removing, storing, and resetting existing pier protection to the lines and grades shown on the plans or established by the Engineer.

MATERIALS:

The materials comprising the existing pier protection system shall be reused if they conform to the materials requirements specified for new pier protection systems and are found to be satisfactory condition as determined by the Engineer. The contractor shall supply all new hardware (splice tongues, plates, nuts, bolts, washers, etc.). Replacement materials shall meet the material requirements of Section 606 of the Standard Specifications. Galvanized railing and posts may be repaired in accordance with Section 719-01, Galvanized Coatings and Repair Methods.

CONSTRUCTION DETAILS:

The Contractor shall remove, store, clean, and reset pier protection and posts as shown on the plans and Standard Sheets or as directed by the Engineer. Holes shall be backfilled with a suitable material and compacted in a manner approved by the Engineer.

METHOD OF MEASUREMENT:

Resetting pier protection will be measured as the number of linear meters of pier protection reset. The measurement will be taken along the top centerline of the steel box beam between the pay limits shown on the plans or Standard Sheets.

BASIS OF PAYMENT:

The unit price bid per linear meter for resetting pier protection shall include the cost of furnishing all labor, equipment, and materials necessary to complete the work.

Any materials damaged due to the Contractor's operation shall be replaced at no additional cost to the State.