

**ITEM 11606.90 - CONCRETE MEDIAN BARRIER TRANSITION (CAST IN PLACE)**

**DESCRIPTION :**

This work shall consist of the replacement of the concrete median barrier removed for the construction of overhead sign structure as shown on the plans.

**MATERIALS:**

Materials shall conform to the applicable provisions of Section 606-2.  
Premoulded Resilient Joint Filler shall conform to Section 705-07.

**CONSTRUCTION DETAILS:**

Construction details shall conform to the applicable provisions of Section 606-3.

**METHOD OF MEASUREMENT:**

The quantity of concrete median barrier transition measured for payment will be the number of meters placed in accordance with the plans and specifications, measured along the axis of the barrier and between its extreme outer limits.

**BASIS OF PAYMENT:**

The unit price bid per meter for the above work shall include the cost of all labor, equipment and material necessary to complete the work, including the cost of premoulded joint filler and any repairs required to the existing barrier.

*Payment will be made under:*

<b>Item No.</b>	<b>Item</b>	<b>Pay Unit</b>
11606.90	Concrete Median Barrier Transition(Cast in Place)	Meter