

ITEM 01607.0641 M - SNOW FENCING FOR BRIDGES (STATE SUPPLIED)

DESCRIPTION

The work shall consist of installing fencing supplied by the State. Fencing shall be installed according to the details and at the locations indicated on the Contract Plans.

MATERIALS

None specified.

CONSTRUCTION DETAILS

Fencing will be supplied by the State and transported to the job site from the location indicated in the contract documents by the contractor.

Fence fabric shall be firmly attached to the posts, rails, and braces. All fencing shall be stretched taut.

The posts shall be fastened to the structure in accordance with the details indicated on the Contract Plans. Posts shall be set so that straight sections are truly vertical.

All the top rails shall pass through the base of the post caps. Both the top and bottom rails shall provide continuous support for the fencing from end-to end of the fence fabric. Sections of both rails shall be joined with sleeve couplings. At expansion joints in the structure, expansion sleeves shall be used. Top rails shall be securely fastened to terminal posts by means of rail end connectors approved by the Engineer.

Horizontal braces shall be provided at all terminal posts, midway between the top and bottom rails, and shall extend from the terminal post to the first adjacent intermediate post. Braces shall be securely fastened to the intermediate posts by brace ends and brace bands. Braces shall be securely fastened to the terminal posts by rail end connectors, approved by the Engineer. Braces shall be made from the same material as the top and bottom rails.

All welding shall meet the requirements of the New York State Steel Construction Manual.

Field welding shall be allowed only where indicated on the Contract Plans, or where ordered by the Engineer. Remove galvanizing in the area of the weld, prior to welding.

All finished surfaces of welds, and surfaces from which the galvanizing has been removed, shall be repaired in accordance with the requirements of Subsection 719-01. All galvanizing repair shall be done at no additional cost.

Unless otherwise noted on the plans:

1. The fabric shall be securely fastened to all terminal posts by 25 mm x 19 mm tension bars with 11 gauge pressed steel bands spaced approximately 300 mm apart.
2. Fabric shall be attached to top and bottom rails with 6 gauge tie wires at 600 mm centers.
3. The fabric shall be securely fastened to all vertical posts by 6 gauge aluminum ties at 300 mm centers.
4. Whenever fencing is cut to fit, the exposed ends, shall be coated as dictated by galvanizing repair procedures in subsection 719-01 of the standard specifications.

METHOD OF MEASUREMENT

ITEM 01607.0641 M - SNOW FENCING FOR BRIDGES (STATE SUPPLIED)

Measurement will be taken as the number of linear meters of fencing installed. Measurement will be taken along the bottom of the bottom rail, center-to-center of terminal posts.

BASIS OF PAYMENT

The unit price bid per linear meter shall include the cost of furnishing all labor, materials, and equipment necessary to complete the work.