

**ITEM 607.1004 11 - REMOVE, STORE AND REINSTALL EXISTING STEEL  
PIPE SWING GATE**

**DESCRIPTION**

This work shall consist of removing, storing and reinstalling existing swing gates in accordance with the contract documents and as directed by the Engineer.

**MATERIALS**

Materials shall be salvaged and reused in reinstalling the gate. Materials damaged or lost by the Contractor and those components of the gate which by nature of their construction are not suitable for reuse, shall be replaced in kind by the Contractor at no expense to the State. Such new materials shall conform to the following subsections of the NYSDOT Standard Specifications:

Structural Steel:	715-01
Concrete:	501
Reinforcing Steel:	709
High Strength Bolts, Nuts and Washers:	715-14
Timber and Lumber:	712-13

**CONSTRUCTION DETAILS**

The locations of the existing gates to be removed, stored and reinstalled shall be as shown on the Contract plans or as ordered by the Engineer. The Contractor shall carefully remove the existing gate and provide safe storage of the salvaged material until reuse. The salvaged gate and related components shall be reinstalled at the same location as before, as shown on the contract plans or as ordered by the Engineer. Gate posts shall be plumb and true to line and grade.

**METHOD OF MEASUREMENT**

This work will be measured as the number steel pipe swing gates satisfactorily removed, stored and reinstalled.

**BASIS OF PAYMENT**

The unit price bid shall include the cost of furnishing all labor, materials, and equipment necessary to satisfactorily complete the work. Progress payments for the work under this item will be made as follows: 50% for the removal of the gate and the remaining 50% upon the satisfactory reinstallation of the gate.