

## **ITEM 10607.21 M - REMOVING CHAIN LINK FENCE**

### **DESCRIPTION**

The Contractor shall remove existing chain link fence in accordance with the plans, specifications and orders of the Engineer.

### **MATERIALS**

Fencing hardware shall conform to the requirements of Subsection 710-10.03 except that aluminum alloy fittings shall not be used.

### **CONSTRUCTION DETAILS**

The Contractor shall remove and dispose of the existing chain link fence as indicated on the plans or ordered by the Engineer. This shall include the removal of the existing concrete footings on the fence post and backfilling with suitable material. All excavation and backfill shall conform to Section 203 - "Excavation and Embankment."

The existing fence shall be removed to the point indicated on the plans or as ordered by the Engineer and the remaining end section of the fence modified to adequately secure the fencing. This section shall be modified to include brace wires and rods, stretcher bars, bands, etc. to secure the fencing in a manner similar to the existing end section or as ordered by the Engineer. Parts salvaged from the removed portion acceptable to the Engineer may be used in the end sections. Additional hardware as required shall be furnished by the Contractor.

### **METHOD OF MEASUREMENT**

This work will be measured by the actual number of meters of fence removed in accordance with the plans or as directed by the Engineer. An additional three meters allowance will be paid for each end section modified to secure the remaining fence.

### **BASIS OF PAYMENT**

The unit price bid per meter for the above work shall include the cost of all labor, equipment and materials necessary to complete the work, including the cost of any fill required to fill the post holes.