

## **ITEM 607.9402—10 – REMOVE AND RESET TIMBER FENCE**

### **DESCRIPTION**

This work shall consist of removing existing timber fencing and resetting of the same fencing in accordance with the Plans, Specifications and as specified by the Engineer.

### **MATERIALS**

All new fencing hardware shall comply with the requirements of the Standard Specification 594-2 Materials.

### **CONSTRUCTION DETAILS**

The Contractor shall carefully remove the existing timber fencing as specified by the Engineer. In addition, all provisions of the construction details of Subsection 594-3, Construction Details, shall apply or as directed by the Engineer.

The Contractor shall supply all additional fence hardware, etc., necessary to supplement the existing materials so that the reset fence will conform to the details shown on the Plans for timber fencing. The materials supplied shall conform in type to the existing fence being relocated.

Any fence damaged in handling and placing shall be replaced at the Contractor's expense.

### **METHOD OF MEASUREMENT**

The quantity to be paid for will be the number of linear meters of timber fencing measured along the top of fencing center to center of end posts, reset in place as shown on the Plans and directions of the Engineer.

### **BASIS OF PAYMENT**

The unit price bid per linear meter shall include the cost of furnishing all labor, materials and equipment necessary to complete the work including, excavation, backfilling, handling, transportation, fence hardware and all incidentals necessary to complete the work.

The cost of removing and disposing of any fence which is not to be reset shall be included in the price bid for Clearing and grubbing. If such item is not part of the Contract, then the cost for fence removal shall be as shown on the Plans.