

ITEM 08607.96 M - REMOVE AND DISPOSE OF EXISTING FENCE

DESCRIPTION:

The contractor shall remove existing fence in accordance with the plans, specifications and directions of the Engineer. All references to "fencing" shall include existing gates, if any to be removed.

MATERIALS:

Materials needed for modifying end sections shall conform to the requirements of Section 710 of the Standard Specifications or shall conform to the material requirements of the existing fence, as directed by the Engineer.

Concrete for footings shall conform to Section 607-2.01 of the Standard Specifications.

CONSTRUCTION DETAILS:

The contractor shall remove and dispose of the existing fence to a point shown on the plans or where directed by the Engineer. If a portion of the existing fence is to remain, the remaining end section shall be modified to adequately secure the fencing. This modified section shall include all hardware necessary to secure the fencing in a manner similar to the existing end section or as directed by the Engineer. Parts salvaged from the removed portion, acceptable to the Engineer, may be reused in the end section.

All work shall be done in a workmanlike manner with care taken not to disturb the surrounding area or existing fence to remain. Any damage to the area or existing fence to remain caused by the contractor's operations shall be repaired to the original condition at no expense to the state. Any concrete post footings shall be either broken up and removed or removed in one piece as determined by the contractor and approved by the Engineer. All post holes shall be filled to meet existing grade. All excavation and backfill shall conform to Section 203 "Excavation and Embankment".

METHOD OF MEASUREMENT:

This work will be measured as the number of meters of fence removed in accordance with the plans or as directed by the Engineer. An additional 3 meter allowance will be paid for each end section modified to secure the remaining fence.

BASIS OF PAYMENT:

The unit price bid shall include the cost of all labor, equipment and materials necessary to complete the work, including the cost of any fill required to fill the post holes.