

ITEM 03607.9901 M - REMOVE AND RELOCATE FENCING

DESCRIPTION

Under this item the Contractor shall remove and relocate fencing where shown on the plans and as ordered by the Engineer. All work shall be done in accordance with these specifications and the applicable Standard Sheets and in reasonably close conformity with the lines and grades shown on the plans or established by the Engineer. All excess or unusable fencing materials removed shall become the property of the Contractor and shall be disposed of by him off the contract site.

All reference to "fencing" shall include existing gates, if any, to be relocated.

Unless otherwise shown on the plans, each section of fence relocated under this item shall be similar in all details to the existing fence it replaces.

MATERIALS

Existing posts, fence fabric, top rails, braces, fittings, wire and gates in satisfactory condition, shall be used for the relocated fences and gates.

Should any new materials be required by order of the Engineer, they shall meet the requirements of Section 710 of the Standard Specifications for the type of fence being relocated.

CONSTRUCTION DETAILS

- a. Fence Removal: The Contractor shall carefully remove the existing fence and clean and store all materials for reuse. The individual concrete post footings shall be broken up and removed and the posts carefully cleaned and stored. All work shall be done in a workmanlike manner with care taken not to disturb the surrounding area and existing fence to remain. Any damage done to the area or existing fence to remain, caused by the Contractor's operations, shall be repaired to the original condition at no expense to the State. All post holes shall be filled to meet existing grade.
- b. Fence Relocation: The applicable Construction Details of Subsection 607-3 of the Standard Specifications, and those on the appropriate Standard Sheet for fencing shall apply.

METHOD OF MEASUREMENT

This item will be measured by the number of linear meters of relocated fencing, including relocated gates. Measurement will be made along the top of fencing, center to center of end posts, properly installed in accordance with the requirements of the plans, specifications, Standard Sheets and directions of the Engineer. An allowance of 3 linear meters will be added for each end post, corner post and pull post installed in accordance with the applicable Standard Sheet.

BASIS OF PAYMENT

The unit price bid per linear meter shall include the cost of furnishing all labor, materials, tools and equipment necessary to satisfactorily complete the work, including removal and disposal of excess fencing not relocated.