

ITEM 09607.9901 M - REMOVE AND STORE SNOW FENCING

DESCRIPTION:

This work shall consist of the removal and storage of snow fencing in locations shown on the Plans, described in the proposal and directed by the Engineer.

MATERIALS:

Existing materials shall be salvaged and stored. Materials damaged or lost by the Contractor, except those few components of the fencing which by nature of their construction are not suitable for reuse, shall be replaced in kind by the Contractor at his expense.

CONSTRUCTION DETAILS:

The locations and limits of the existing fencing to be removed shall be as authorized by the Engineer. The Contractor shall carefully dismantle and remove the existing fencing and provide safe storage of the salvaged materials until picked up by State Forces.

METHOD OF MEASUREMENT:

The quantity to be paid for under this item will be measured by the actual number of linear meters of fencing removed and stored.

BASIS OF PAYMENT:

The unit price bid per linear meter shall include the cost of furnishing all labor, materials and equipment necessary to remove and provide safe storage of the fencing.