

ITEM 08608.0102 M - REMOVAL AND REPLACEMENT OF CONCRETE SIDEWALK AND SUBBASE COURSE

- G. Material removed under this item shall be disposed of in conformance with the provisions of § 203-3.08 of the Standard Specifications.

METHOD OF MEASUREMENT:

This work will be measured as the number of square meters of satisfactorily placed concrete sidewalk, as approved by the Engineer, and as computed from payment lines as detailed in the contract documents, and as directed by the Engineer.

BASIS OF PAYMENT:

The unit price bid shall include the cost of furnishing all labor, materials, and equipment necessary to complete the work. The cost of sawcutting shall be include in the cost of this item.

- A. Progress payments for the removal and replacement of concrete sidewalk and subbase shall be as follows:

90 % - When the existing sidewalk and subbase have been removed, and the new subbase and sidewalk have been satisfactorily placed, as determined by the Engineer.

10 % - Upon removal of forms, completion of a 4 day curing period, cleanup, and necessary regrading and seeding , as directed by the Engineer.