

**ITEM 10608.0105 M - CONCRETE SIDEWALKS - UNREINFORCED
(GRADING INCLUDED)**

DESCRIPTION. The work shall consist of the construction of portland cement concrete sidewalks and necessary grading as shown on the plans.

MATERIALS. The following requirements of Sections 203 and 608 shall apply: 203-2.02A, 608-2, and 608-2.01.

CONSTRUCTION DETAILS. The requirements of Subsection 203-3.12 shall apply to the placement of embankment.

The requirements of Subsection 608-3.01 shall apply except that all references to driveways and wire fabric for reinforcement shall be disregarded. The sidewalk shall be constructed without wire fabric for concrete reinforcement.

The location of the sidewalks shall be properly graded to conform with the sidewalk cross-section and line and grade. The graded area shall be firm and dry before placing the concrete and all organic or unsuitable materials, existing curbs, sidewalks, and driveways shall be removed.

METHOD OF MEASUREMENT. Concrete sidewalks will be measured by the number of cubic meters of cement concrete computed from payment lines shown on the plans.

BASIS OF PAYMENT. The unit price bid per cubic meter will include all excavation, embankment, preparation of subgrade, and all other materials, equipment, and labor necessary to complete the work as called for on the plans and to the satisfaction of the Engineer.

No separate payment will be made for excavation or embankment above, below, or within the volume of sidewalk placed.

Payment at the unit bid price will be made after the concrete sidewalks and curing application have been properly placed.