

## **ITEM 09608.0106 M - CONSTRUCTING CONCRETE SIDEWALK CURB RAMPS**

**DESCRIPTION:** The contractor shall remove curb and necessary sidewalk and subgrade materials at locations identified in the contract documents or directed by the EIC and as necessary, replace curb, subgrade materials and pour or place new sidewalk curb ramp conforming to the most current Standard Sheets or as directed by the EIC.

**MATERIALS:** The material requirements of the following sections of the Specifications shall apply, unless otherwise specified in the contract documents or directed by the ENGINEER.

**Subbase Course** - Section 304 - 2, Subbase Course, Optional Type except Type 1 material used under option B shall have 98% to 100% of material by weight passing the 50 mm sieve.

**Asphalt or Concrete Sidewalk** - Section 608 - 2.

**Asphalt Pavement and Tack Coat** - Sections 403-2 and 407-2.

**Concrete Curb and Stone Curb** - Section 609-2, Type VF150 Conventionally Formed or Precast Concrete Curb or granite curb.

**CONSTRUCTION DETAILS:** The Contractor shall perform the necessary work to construct sidewalk curb ramps in accordance with Sections 107, 206, 304, 403, 407, 608, and 609 of the Specifications .

Maintenance and Protection of Traffic (MPT) shall be in accordance with the current NYS Manual of Traffic Control Devices as required for individual work locations. The cost of providing for MPT shall be included in MPT items in the contract except where no Items are specified, cost of work shall be included in this item.

**METHOD OF MEASUREMENT:** Concrete sidewalk curb ramps shall be measured in square meters of curb ramp surface area estimated to the nearest one tenth of a square meter within the curb ramp limit, including curb and area of road pavement repairs as determined by limits of saw cuts and/or form work that define the curb ramp work limits. This item shall not be used to replace sections of sidewalk beyond the curb ramp limits. The construction of the Detectable Warning Field on the ramp shall not be included in this item.

**BASIS OF PAYMENT:** The unit price bid shall include the cost of all equipment, materials and labor necessary to complete the work including, but not limited to saw cutting, excavation, disposal, compaction, forming, subbase material, concrete sidewalk construction, curb sawing, milling or reconstructing, pavement repairs and restoration and/or replacement of disturbed areas beyond the work limit. The construction of the Detectable Warning Field on the ramp will be paid under separate item. No other separate payment shall be made for work relating to this item unless otherwise specified in the contract documents.