

**ITEM 10608.0205 M - ASPHALT CONCRETE SIDEWALKS,
DRIVEWAYS AND BICYCLE PATHS (GRADING
INCLUDED)**

DESCRIPTION.

The work shall consist of the construction of asphalt concrete sidewalks, driveways, and bicycle paths and necessary grading as shown on the plans.

MATERIALS.

The following requirements of Sections 203 and 608 shall apply: 203-2.02A, 608-2, and 608-2.02.

CONSTRUCTION DETAILS.

The requirements of Subsection 203-3.12 shall apply to the placement of embankment.

The requirements of Subsection 608-3.02 shall apply in addition to the following:

The location of asphalt concrete sidewalks, driveways, and bicycle paths shall be properly graded to conform with the sidewalk, driveway, or bicycle path cross-section and line and grade. The graded area shall be firm and dry before placing the asphalt and all organic or unstable materials, existing curbs, sidewalks, and driveways shall be removed.

METHOD OF MEASUREMENT.

This work will be measured by the number of metric tons of asphalt concrete furnished and incorporated in the work.

BASIS OF PAYMENT.

The unit price bid per metric ton shall include all excavation, embankment, preparation of subgrade, and all other materials, equipment, and labor necessary to complete the work as called for on the plans and to the satisfaction of the Engineer.

No separate payment will be made for excavation or embankment above, below, or within the volume of asphalt concrete sidewalks, driveways, and bicycle paths placed.