

ITEM 02608.03 M - PRECAST CONCRETE PAVERS ON EXISTING SUBBASE

Description

The work consists of furnishing and placing precast concrete pavers in the locations as indicated in the contract documents and where directed by the Engineer.

Materials

Manufactured by: Concrete Stone & Tile Corp.
Colorful & Creative Concrete Pavers
23 Ridge Road
P.O. Box 2191
Branchville, NJ 07826
Size = 6CM2

Unless otherwise specified in the contract documents, materials shall meet the requirements of 704-13, Precast Concrete Pavers.

Sizes, shapes, and colors shall be as specified in contract documents and approved by the Engineer prior to the beginning of work under this item.

Material for setting bed and joint filler shall be stone screenings, meeting the requirements of 703-02, Coarse Aggregate-Screenings.

Construction Details

Fine Grade Existing Subbase course prior to placing bedding material. Precast concrete pavers shall be laid on a properly prepared 50 mm setting bed of stone screenings over the subbase and specified subgrade. The pavers shall be laid in patterns and at the elevations indicated in contract documents or as directed by the Engineer and shall provide a uniformly even surface.

After the pavers are in place, joint filler shall be swept over the pavers until the joints are completely filled.

Unless otherwise specified in the contract documents, or directed by the Engineer, the Contractor shall install the pavers in accordance with the manufacturer's recommended procedures.

Method of Measurement

Precast concrete pavers shall be measured by the number of square meters acceptably placed as indicated in contract documents or as directed by the Engineer.

Basis of Payment

ITEM 02608.03 M - PRECAST CONCRETE PAVERS ON EXISTING SUBBASE

The unit price bid per square meter shall include the cost of all labor, materials, and equipment necessary to complete the work, including fine grading of existing subbase and except that any necessary excavation and new subgrade course will be paid for under their appropriate items.

This specification has been
Disapproved by EI 04-019