

ITEM 08608.0304 M - REMOVE, STORE AND RESET CONCRETE BLOCK PAVERS

DESCRIPTION:

Under this item the contractor shall carefully remove, store and reset concrete block pavers in the locations shown on the plans, or as directed by the Engineer.

MATERIALS:

Pavers shall be the units salvaged in a usable condition as determined by the Engineer.

Damaged pavers shall be replaced with new pavers of the same size, shape and color as the existing pavers as determined by the Engineer. Materials shall meet the requirements of Section 704-13, Precast Concrete Pavers.

Setting bed material for the reset concrete block pavers shall conform to the requirements of Subsection 608-2.05.

CONSTRUCTION DETAILS:

All pavers shall be laid in the same pattern as existed or as directed by the Engineer to provide a uniformly even surface. Pavers shall be laid on a granular material setting bed not to exceed 50 mm of uniformly compacted material placed over the specified subbase.

After the pavers are in place, joint filler shall be swept over the pavers until the joints are completely filled.

METHOD OF MEASUREMENT:

Concrete block pavers shall be measured by the number of square meters of reset pavers. Damaged pavers shall be replaced by the contractor at his own expense. Unused concrete pavers shall be removed and disposed of under Item 203.02.

BASIS OF PAYMENT:

The unit price bid per square meter shall include the cost of all labor, materials and equipment necessary to complete the work. Excavation and subbase course necessary to reset the pavers, and removed unused pavers will be paid for under their appropriate items.