

Item 02608.10 M - CLEANING & REPAIR OF STONE BLOCK PAVING

Description

This work shall consist of cleaning by removing and disposing of all debris, litter, sand, dirt, weeds, other vegetative material, and other material foreign to the stone block pavement areas. This work also includes repairing the areas by replacing to original condition any loose, missing, or "popped out" blocks and mortar.

Materials - See Section 608-2 of Standard Specifications

Stone Block: 704-09 and existing, on site, if in good condition.
New, 4 x 4 x 4" pink granite, split face.
Submit sample for approval.

Herbicides: 713-13 and as approved.

Construction Details

Contractor shall propose method to restore block paving to original condition to E.I.C. for approval at least 2 weeks prior to proposed commencement of operation. Method shall not cause degradation or burden to the enclosed highway drainage. Method and equipment shall be safe for the adjacent traveling public, property owners, and remaining intact pavers. All debris or excess material shall be disposed of in accordance with Department of Environmental Conservation Regulations. Any blocks disturbed by cleaning method shall be repaired.

Debris falling into roadway shall be removed immediately.

Loose or punky mortar shall be removed to the extent ordered by the Engineer. Contaminated setting bed material shall be removed, replaced, and compacted to level necessary to reset block. Missing blocks shall be replaced in the pattern of the surrounding blocks with matching mortar joints and in accordance with Section 608-10 of the Standard Specifications.

If the method chosen includes the initial use of herbicides, they must be applied by a licensed applicator. An herbicide application to the entire cleaned area, at rate, type, and method approved by E.I.C. shall occur after all cleaning and repairing is completed.

Method of Measurement

Payment will be made on a square meter basis. It shall include cleaning at the top and bottom of curbs.

Basis of Payment

The price bid per square meter shall include all materials, equipment, labor, excavation, and disposals necessary to complete the work.