

**ITEM 608.1004 05 - REMOVE, RESET OR REPLACE EXISTING STONE
BLOCK PAVING**

DESCRIPTION

The Contractor shall carefully remove the existing stone block paving from its original and/or present position, regrade or replace the existing bedding, replace any missing block and clean and reset existing block in accordance with these specifications, as shown on the plans, or as directed by the Engineer.

MATERIALS

Stone block paving from the existing worksite will be reused. Any stone block paving within the project limits which will be removed and replaced with other treatments (Portland cement concrete, asphalt concrete, sod) may be used to replace missing blocks in accordance with these specifications as shown on the plans or as directed by the Engineer. All new and reused stone block paving required to complete the reconstruction work shall match the existing in kind, quality, texture, color, and finish. The Contractor shall submit samples of new stone block paving to the Engineer for approval.

Any new block or bedding material shall conform to the requirements set forth in Subsection 608-2.04 of the Standard Specification.

CONSTRUCTION DETAILS

The Contractor shall remove the existing stone block paving from areas shown on the plans or as ordered by the Engineer. All existing block shall be cleaned of mud, sand, and grout to the satisfaction of the Engineer. All block shall be stored and protected in an area approved by the Engineer. Any block that is damaged in removal, storage, and resetting or lost in any way shall be replaced at the Contractor's expense. Any block rejected by the Engineer shall become the property of the Contractor for disposal.

All stone block shall be placed using the same pattern and orientation as existing before removal as shown in the plans and in accordance with the requirements of Subsection 608-3.04, Grouted Stone Block Paved Sidewalks and Driveways, using sand-cement mixture for bedding.

METHOD OF MEASUREMENT

The quantity of removing, resetting, or replacing stone block paving shall be the number of square meters of stone block paving actually reset or replaced, measured along the plane of the exposed surface of the block.

BASIS OF PAYMENT

The unit price bid per square meter shall include the cost of furnishing all labor, materials, and equipment necessary to satisfactorily complete the work. This includes the new sand-cement bedding, new stone blocks needed to replace missing blocks damaged by the Contractor's operations, along with any necessary excavation.

No payment will be made for stone block paving removed and disposed of.