

ITEM 09608.11 M - REMOVING AND STORING FLAGSTONE SIDEWALK

DESCRIPTION:

Under this item the Contractor shall carefully remove and store the existing flagstone sidewalk. The salvaged flagstones shall be stored on the project site in a manner and at locations as noted on the plans or as directed by the Engineer.

MATERIALS:

All flagstones salvaged shall be in a re-useable condition as determined by the Engineer.

CONSTRUCTION DETAILS:

The Contractor shall remove and neatly store the existing flagstone sidewalk according to the procedures outlined on the plans or as directed by the Engineer. The work shall be done in such a manner as to preserve intact sections. Damaged or unusable sections shall be disposed of by the Contractor. Proper precautions shall be taken to protect pedestrian and vehicle traffic at all times.

METHOD OF MEASUREMENT:

The quantity to be measured under this item shall be the number of square meters of flagstone sidewalk removed and stored.

BASIS OF PAYMENT:

The unit price per square meter shall include the cost of all labor, material and equipment necessary to properly complete the work.