

**02608.1201 - INSTALL PRECAST CONCRETE BLOCK PAVED SIDEWALKS AND DRIVEWAYS**

**DESCRIPTION:**

This work shall consist of installing precast concrete paver blocks supplied by the New York State Department of Transportation. All work shall be in accordance with these specifications and in reasonably close conformity with the lines and grades shown on the plans or established by the Engineer .

**MATERIALS** Concrete block pavers are available for pick up at a location stated in the plans.

Concrete Sand	703-07
Water	712-01
Sealer	Described in the plans

All Other Requirements shall meet the standard specifications § 608.12Materials

**CONSTRUCTION DETAILS:**

All requirements of § 608-3.05 of the Standard Specifications Shall Apply.

**METHOD OF MEASUREMENT**

All requirements of § 608-4.05 of the Standard Specifications Shall Apply.

**608-5 BASIS OF PAYMENT**

**608-5.05 Precast Concrete Block Paved Sidewalks and Driveways.** The unit price bid per square meter shall include the cost of all labor, equipment and materials necessary to complete the work, including loading, unloading and transportation of the precast concrete block pavers from the storage location to the project work site, setting bed / joint material and sealer. Any necessary excavation and subbase course will be paid for under the appropriate items .