

608.1202 11 M - PRECAST CONCRETE PAVERS ON MORTAR SETTING BED

DESCRIPTION:

This work shall consist of furnishing and installing precast concrete pavers on a mortar setting bed in accordance with the contract documents and as directed by the Engineer.

MATERIALS:

Precast concrete pavers shall conform to the requirements of Section 704-13 of the Standard Specifications (Metric Edition.)

Prior to the start of work, the Contractor shall submit samples of each type and color of paver specified in the contract documents for approval by the Engineer in coordination with the Regional Landscape Architect. The samples shall be clearly labeled with the Contract Number, manufacturer, color and finish. All pavers used on the work shall conform to the approved samples.

CONSTRUCTION DETAILS:

Construction shall be as per Section 608-3.05 Precast Concrete Block Paved Sidewalks and Driveways, except precast concrete pavers shall be placed on a mortar setting bed.

METHOD OF MEASUREMENT:

This work will be measured for payment as the number of square meters of Precast Concrete Pavers on Mortar Setting Bed satisfactorily furnished and installed.

BASIS OF PAYMENT:

The unit price bid for Precast Concrete Pavers on Mortar Setting Bed shall include the cost of furnishing all labor, materials, and equipment necessary to satisfactorily complete the work.