

ITEM 01608.21 M - PORTLAND CEMENT CONCRETE SIDEWALK AND SIDEWALK RAMP, COMPLETE

The requirements of Section 608 entitled Sidewalks, Driveways, Bicycle Paths, Brick Paving, Grouted Stone Block Paving, and Precast Concrete Paving of the Standard Specifications, shall apply except as modified and/or revised below.

DESCRIPTION:

The work shall include necessary excavation and subbase course to construct the portland cement concrete sidewalk ramp in accordance with the details shown on the plans.

MATERIALS:

Subbase material shall meet the requirements of Subsection 304-2, Materials of the Standard Specifications.

CONSTRUCTION DETAILS:

Excavation. The provisions of Subsections 206-1.01, General and 206-3, Construction Details of the Standard Specification shall apply.

Subbase Course. The provisions of Subsections 304-1.01, General and 304-3, Construction Details of the Standard Specifications shall apply.

METHOD OF MEASUREMENT:

Portland cement concrete sidewalk and sidewalk ramps will be measured as the number of square meters of cement concrete sidewalk and/or sidewalk ramps placed as shown in the Contract Documents or as directed by the Engineer.

BASIS OF PAYMENT:

The unit price bid per square meter shall include the cost of necessary excavation, furnishing and placing the subbase, preparing the subgrade, furnishing and placing concrete sidewalks and sidewalk ramps, equipment and labor necessary to complete the work as specified.

No separate payment will be made for excavation and subbase and the cost of this work is to be included in the price bid for the portland cement concrete sidewalks and sidewalk ramps.

Curb as indicated on the plans, will be paid for under its respective item.