

ITEM 08609.06 M - CURB REMOVAL

DESCRIPTION:

Under this item the contractor shall remove and dispose of various types of existing curb where indicated on the plans or where directed by the Engineer.

MATERIAL:

Not specified.

CONSTRUCTION DETAILS:

The existing curbs shall be removed and disposed of in a neat and workmanlike manner.

The existing curbs to be removed are adjacent to existing pavements that are to remain, the contractor shall exercise extreme care during their removal so as not to damage the existing adjacent facilities in any way. In the event that such damage does occur as a direct result of the contractor's curb removal operation, repairs shall be made by the contractor to these existing facilities at no cost to the State and in a manner satisfactory to the Engineer.

Existing longitudinal tie bars are to be removed and disposed of in areas where new construction abuts the existing pavements that are to remain.

METHOD OF MEASUREMENT:

This work will be measured as the number of meters of existing curbs removed and disposed of, measured along their center line and within the limits indicated on the plans or where directed by the Engineer.

BASIS OF PAYMENT:

The unit price bid per meter shall include the cost of all labor and equipment necessary to complete the work, including the removal and disposing of the existing longitudinal tie bars.