

ITEM 63609.13XX M - OPTIONAL CONCRETE CURB, EMERGENCY STANDBY CONTRACT WORK

All the provisions of Section 609 of the Standard Specifications shall apply with the exception of the following:

DESCRIPTION:

This work shall consist of the construction of concrete curb in accordance with these specifications and the lines and grades shown on the Plans or established by the Engineer.

For summer work the Contractor shall have the option of selecting the method of furnishing and placing concrete curb as follows:

- Conventionally formed or machine formed concrete curb (type AB, AC, BB, BC as indicated).
or
- Precast concrete curb.

Summer work is defined as work performed from April 15th through the third Saturday in October and winter work is defined as work performed during the remainder of the year.

For winter work the contractor will be required to use precast concrete curb.

CONSTRUCTION DETAILS:

For summer work the Contractor shall select one of the optional methods of curb construction and use it in all locations unless otherwise approved in writing by the Regional Director. The curb shall conform to the size and shape shown on the Standard Sheet unless otherwise indicated on the Plans. The curb shall be constructed on a foundation as shown on the Plans or the Standard Sheet.

BASIS OF PAYMENT:

Payment will be made under:

<u>ITEM NO.</u>	<u>ITEM DESCRIPTION</u>	<u>PAY UNIT</u>
63609.1301M	Optional Concrete Curb, Emergency Standby Contract Work, Quantity Range 1 (0 to 14.9)	m
63609.1302M	Optional Concrete Curb, Emergency Standby Contract Work, Quantity Range 2 (15 to 29.9)	m
63609.1303M	Optional Concrete Curb, Emergency Standby Contract Work, Quantity Range 3 (30 to 60)	m