

ITEM 10609.19 M - DECREASE HEIGHT OF EXISTING CONCRETE CURB

DESCRIPTION. Under this item the Contractor shall decrease the height of the existing concrete curb at the locations indicated on the plans.

MATERIALS. Not specified.

CONSTRUCTION DETAILS. The Contractor shall have the following options:

- a. Decrease the curb height as shown on the plans by grinding down the top section of the existing curb with a machine approved by the Engineer.
- b. Decrease the curb height as shown on the plans by saw cutting the existing curb along a horizontal plane with a machine approved by the Engineer.

All curb, sections of curb, slurry or residue resulting from curb operations shall be removed from the construction site and disposed of by the Contractor.

The equipment used to reduce the height of the concrete curb shall be capable of producing a finished product which is within 6 mm of the height specified on the plans and shall produce a finished surface texture acceptable to the Engineer. Any material which spills onto the roadway during the operation shall be immediately removed. Any other removed material which causes objectionable dust as determined by the Engineer shall be immediately disposed of.

The Contractor shall provide equipment to control dust and any other particulate matter created by the curb height reduction operation. This equipment shall be subject to the approval of the Engineer.

The Contractor also shall provide equipment to pick up the removed material without producing dust which, in the opinion of the Engineer, is objectionable. This equipment shall be subject to the approval of the Engineer.

Any existing concrete curb to remain which the Engineer deems to have been excessively damaged by the Contractor shall be removed and replaced to the satisfaction of the Engineer.

METHOD OF MEASUREMENT. This work will be measured by the number of meters of curb modified. The measurement will be taken to the nearest meter along the top front arris line of the remaining curb.

BASIS OF PAYMENT. The unit price bid per meter shall include the cost of all labor, materials, and equipment necessary to complete the work. No payment will be made for removal and replacement of curb damaged by the Contractor.