

ITEM 15609.40 M - REINFORCED PRECAST CONCRETE PARKING BLOCKS

Description: Under this item, the Contractor shall furnish and place Reinforced Precast Concrete Parking Blocks of the type detailed below at the location indicated on the plans or where directed by the Engineer.

Materials: All the provisions of §714-04 Precast Concrete Curb shall apply including those under sampling and testing.

Construction Details: The blocks shall be set true to line and grade on the existing pavement.

Attachment, to the existing pavement, shall be made with 22 mm round anchor pins, 600 mm in length. The pins shall be driven flush with the top of the block.

The blocks shall be placed where indicated on the plans.

The Contractor shall protect the blocks and keep them in first class condition until acceptance of the Contract. Any blocks that are damaged previous to the final acceptance of the work shall be removed and satisfactorily replaced at the Contractor's expense.

Method of Measurement: The quantity to be paid for under this item will be the number of blocks placed in accordance with the plans, specifications and orders of the Engineer.

Basis of Payment: The unit price bid for each block shall include the cost of furnishing all labor, materials and equipment necessary to satisfactorily complete the work, including the anchor pins.

