

ITEM 611.90 10 – REMOVAL AND DISPOSAL OF EXISTING STAKES, GUYS, WRAPPINGS AND ANCHORS

DESCRIPTION

Under this item the Contractor shall remove and dispose of stakes, guys and anchors from trees planted on a previous Contract.

MATERIALS

None specified.

CONSTRUCTION DETAILS

Stakes, guys and anchors shall be removed by a method which will not damage any portion of the tree. The existing saucer shall be restored to proper condition in accordance with Regional Planting Specifications, Standard Specifications 611-3.03A and applicable Standard Sheets. The material removed shall become the property of the Contractor and shall be removed from the project site.

METHOD OF MEASUREMENT

This item will be measured as the number of each tree serviced and accepted.

BASIS OF PAYMENT

The unit price for each tree serviced shall include all labor, equipment, incidentals, and materials necessary to do the work specified.

DISAPPROVED BY E12-000