

## **ITEM 03615.0001nn M - MODULAR NEWSPAPER DISPLAY RACK**

### **DESCRIPTION**

This work shall consist of furnishing and installing modular newspaper display racks, including mounting hardware, in accordance with the Contract Documents and manufacturers specifications, unless otherwise directed by the Engineer.

### **MATERIALS**

The Contractor shall submit product data, shop drawings, and maintenance data to the Engineer for review and approval by the Regional Landscape Architect prior to the purchase of the modular newspaper rack. Drawings and product data shall clearly show all materials, finishes (exterior color and texture), dimensions, number and orientation of newspaper units, support frame type, connections, installation details and type of coin mechanism proposed.

The coin mechanism shall accept combinations of nickels, dimes, quarters and Sacagawea dollar coins.

### **CONSTRUCTION DETAILS**

The modular newspaper display rack shall be installed at the locations shown on the drawings and in accordance with the specifications and recommendations of the manufacturer.

The entire modular newspaper display rack shall be fabricated at the manufacturer's plant and is to be delivered to the job site as a complete unit.

The newspaper rack unit shall be set level and plumb into position by means of bolting the support frame to a concrete surface according to the recommendations of the manufacturer.

After completing the installation of the modular newspaper display rack, the Contractor shall remove spots, dirt and debris from the unit. Damaged finishes or components shall be repaired and/or replaced by the Contractor to the satisfaction of the Engineer.

### **METHOD OF MEASUREMENT**

Modular newspaper display racks shall be measured by the number of units supplied and installed in accordance with the plans, specifications and directions of the Engineer.

### **BASIS OF PAYMENT**

The unit price bid for each modular newspaper display rack shall include the cost of furnishing all labor, materials and equipment necessary to satisfactorily complete the work.

The cost of the concrete mounting surface will be paid for under its appropriate item.

**ITEM 03615.0001nn M - MODULAR NEWSPAPER DISPLAY RACK**

Payment will be made under:

<u>Item</u>	<u>Description</u>
03615.000101	Modular Newspaper Display Rack, One Display
03615.000102	Modular Newspaper Display Rack, Two Display
03615.000103	Modular Newspaper Display Rack, Three Display
03615.000104	Modular Newspaper Display Rack, Four Display
03615.000105	Modular Newspaper Display Rack, Five Display
03615.000106	Modular Newspaper Display Rack, Six Display

DISAPPROVED  
BY EI 12-001