

**ITEM 07615.0102 M – PEDESTAL MOUNTED PICNIC TABLE –
HANDICAPPED ACCESSIBLE**
**ITEM 07615.0103 M – PEDESTAL MOUNTED PICNIC TABLE (WITH
CONCRETE PAD)**

DESCRIPTION

This work consist of furnishing and installing pedestal-mounted picnic tables with concrete footings and pads in accordance with the Contract Documents or as directed by the Engineer.

MATERIALS

The picnic table shall be a pedestal-mounted model. The tables are to have 4 backless seats mounted to the table frame. Handicapped accessible picnic tables shall have seats mounted on only three sides with the fourth side remaining unencumbered for wheel chair access to the table.

The foundation shall be Class A concrete as specified in Section 501, Portland Cement Concrete – General, and shall have a minimum compressive strength of 20,700 kPa at twenty-eight days.

The pads shall be Portland Cement Concrete and shall conform to the provisions of Section 608, Sidewalks, Driveways, Bicycle Paths Paving, Grouted Stone Paving and Precast Concrete Paving.

The contractor shall submit shop drawings and catalog cuts to the Engineer for review and approval by the Regional Landscape Architect prior to the purchase of the picnic table. Drawings shall show clearly all materials, finishes, and connecting and joining methods. The materials used in the fabrication of the picnic tables shall conform to the following requirements:

1. Steel Frame for Picnic Table. The frame shall be fabricated from steel in accordance with ASTM A40. The frame shall be entirely welded. The frame shall be electrostatically powder coated by the manufacturer to produce a baked resin finish. Color shall be selected at the time of shop drawing review. Color chips shall be submitted to the Engineer for selection and approval.

2. Wood Members. The wood members used throughout the picnic tables shall be Clear All Heart Redwood and in accordance with the Standard Specifications for Grades of California Redwood Lumber. The wood members shall be kiln dried, and sanded smooth.

3. Fasteners. All fasteners shall be stainless steel and shall conform to the requirements of Subsection 715-16.

CONSTRUCTION DETAILS

The assembled picnic table shall be installed at the locations shown on the drawings and in accordance with the specifications and recommendations of the manufacturer.

The entire picnic table shall be fabricated at the manufacturer's plant and is to be delivered to the job site as a complete unit.

The table center support shall be permanently set level and plumb into position by means of a concrete footing. Install at the height indicated on the contract plans.

**ITEM 07615.0102 M – PEDESTAL MOUNTED PICNIC TABLE –
HANDICAPPED ACCESSIBLE**
**ITEM 07615.0103 M – PEDESTAL MOUNTED PICNIC TABLE (WITH
CONCRETE PAD)**

The concrete pad shall be constructed and installed as shown in the contract documents.

METHOD OF MEASUREMENT

Picnic tables shall be measured by the number of units supplied and installed in accordance with the plans, specifications and directions of the Engineer.

BASIS OF PAYMENT

The unit price bid for each picnic table, or picnic table with concrete pad, shall include the cost of furnishing all labor, excavation, equipment and materials necessary to satisfactorily complete the work.