

ITEM 02615.0510 M - LITTER RECEPTACLE

Description:

The Contractor shall furnish and install litter receptacles at the locations shown on the plans or as directed by the Engineer, in accordance with the detail in the plans.

Materials:

The materials for this work shall conform to the following requirements, unless otherwise approved.

- A. Trash Can shall be as manufactured by:

Custom Structures Inc.
670 Mercer Road
P.O. Box 1888
Butler, PA 16003
"Harmony II" or "Pullman Tulip" Litter Receptacle models

-OR-

Columbia Cascade Company
Timber Form Site Complements
1975 S. W. Fifth Ave.
Portland, OR 97201-5293
"2811-FT" Litter Container

-OR-

An approved equal.

- B. Portland Cement Concrete. Portland Cement Concrete used for the footings shall meet the requirements for Class A concrete as specified in Section 501, Portland Cement Concrete - General.
- C. Connecting Hardware - as supplied or recommended by the manufacturer or as directed by the Engineer.

Construction Details:

The litter receptacles shall be installed in the positions and manner shown on the plans, according to the manufacturer's instructions, and as approved by the Engineer. There are optional methods of installation shown in the plans and type, quantity and location of each shall be determined prior to the Contractor ordering litter receptacles by the Engineer-in-Charge in consultation with the Regional Landscape Architect and the Owner.

Method of Measurement:

Litter receptacles will be measured as the number installed on an each basis, as shown on the plans or to the satisfaction of the Engineer.

Basis of Payment:

The unit bid price for each litter receptacle shall include the cost of any excavation, preparing base and furnishing all equipment, hardware, materials and labor necessary to complete the work.