

ITEM 10615.0904 M - TRANSPLANTING DECIDUOUS TREES 50mm TO 100mm CAL.

ITEM 10615.0905 M - TRANSPLANTING DECIDUOUS TREES 101mm TO 150mm CAL.

ITEM 10615.0906 M - TRANSPLANTING DECIDUOUS TREES 151mm TO 200mm CAL.

ITEM 10615.0907 M - TRANSPLANTING DECIDUOUS TREES 201mm TO 250mm CAL.

ITEM 10615.0908 M - TRANSPLANTING DECIDUOUS TREES 251mm and greater CAL.

DISAPPROVED  
BY EI 12-001

**DESCRIPTION:** This work consists of digging by hand existing major deciduous trees and transplanting them to locations shown on the contract plans and specified in the field by the Regional Landscape Architect.

This work shall also include all operations necessary to complete the transplanting work as specified. Section 611, Planting Specifications, and the Supplemental Landscape Development Specifications shall apply with the following exceptions.

**MATERIALS:**

A. Trees. Shall be existing trees selected for transplant by the Regional Landscape Architect.

B. Planting Materials. Subsection 611-2.02 shall apply.

**CONSTRUCTION DETAILS:** Subsection 611-3.01 thru 611-3.06 shall apply.

**METHOD OF MEASUREMENT:** Transplanting deciduous trees will be measured by the number of trees of each caliper counted as having been completed and accepted.

**BASIS OF PAYMENT:** Subsection 611-5 shall apply.