

ITEM 07615.10 M - RELOCATION OF INFORMATIONAL KIOSKS

Description

The work shall consist of the relocation of informational kiosks as shown on the plans or as directed by the Engineer.

Materials

The existing kiosks and all necessary connecting and attaching hardware.

Footings shall be class A concrete.

Construction Details

The Contractor shall relocate the informational kiosks from their present location to their new location as shown on the plans or as directed by the Engineer. The kiosks and related hardware shall be stored and protected until their re-installation. It shall be the Contractor's responsibility to repair any damage to the informational kiosks which occurs during the removal, transportation, storage, or installation, at his expense.

Method of Measurement

The work will be measured as the total number of informational kiosks removed, stored and protected, and re-installed, including footings and excavation, as shown on the plans or as directed by the Engineer.

Basis of Payment

The unit price bid for each informational kiosk shall include the cost of all labor, material, and equipment necessary to complete the work.