

ITEM 08615.1001 M - WOOD KIOSK

DESCRIPTION:

This work shall consist of furnishing and erecting kiosk of the type and size and at the location shown on the plans or as directed by Engineer. Construction of the kiosk shall be done in accordance with the specifications and the plans.

MATERIALS:

DISAPPROVED

Material	Quality
<i>Lumber:</i>	
Posts, Built-up Posts, Joists, Rafters, Headers	Pressure Treated Southern Yellow Pine Lumber Grade #1
Facia Board	Red Cedar Lumber Grade 1
Exterior Plywood	Exterior Medium Density Overlay. One Good Side.
Exterior Plywood for Roof	Exterior
Cedar Shakes	Tapersplit Grade #1
<i>Metal Fasteners (Nails, Screws and Bolts)</i>	
Metal Rafter and Joist Support Spider	Hot Dipped Galvanized ASTM A-36 Steel
Steel Post Base	Hot Dipped Galvanized ASTM A-36 Steel. Designed To Accomodate 5030 lbs. Of Uplift.
Steel Plates	Hot Dipped Galvanized ASTM A-36 Steel
Bolts and Carriage Bolts	Hot Dipped Galvanized ASTM A-325 Steel
Nuts	Hot Dipped Galvanized ASTM A-563
Washers	Hot Dipped Galvanized ASTM F-436
Lag Screws, Thread Forming Screws, Drywall Screws	Hot Dipped Galvanized Steel
Aluminum Strap, Flashing, Exhibit Frame	Aluminum
Common Nails, Shingle Nails	Hot-dipped Galvanized Steel
<i>Other Materials (Paint, Concrete, Felt Paper):</i>	
Concrete Footing	555.0104M Footing Concrete, Class A
Asphalt Roofing Felt Paper	Section 712-12 of the Standard Specifications

ITEM 08615.1001 M - WOOD KIOSK

Paint	Material Section 740-02 Painting Timber and Lumber. Color: Exterior Brown to match other Catskill Forest Preserve signs and structures. Color must be approved by Regional Landscape Architect.
Clear Exhibit Covering	Clear Plexiglass

Lumber shall be the size specified on the plans and in accordance with Section 712-14, Stress Graded Timber and Lumber of the Standard Specifications. The southern yellow pine shall be treated in accordance with Section 708-31, Wood Preservative - waterborne.

All steel metal fasteners such as nails, bolts, anchors and screws shall be galvanized in accordance with Section 719-01, Galvanized Coating and Repair Methods.

CONSTRUCTION DETAILS:

Kiosk with footings shall be constructed and installed as shown on the plans, and as approved by the Engineer.

METHOD OF MEASUREMENT:

The quantity to be paid for shall be the number of units furnished and placed in accordance with the plans.

BASIS OF PAYMENT:

The unit price bid shall include the cost of all labor, equipment and materials necessary to complete the work.