

## **ITEM 01615.1004 - INTERPRETIVE EXHIBIT PANEL**

### **DESCRIPTION**

The work shall consist of fabricating and furnishing interpretive exhibit panels where indicated in the contract documents and as ordered by the Engineer. Panels shall consist of a combination of interpretive information with text, photos, illustrations and orientation maps.

**Submittals:** Interpretive Panel size, finish and colors shall be approved in writing by the Engineer prior to manufacturing the panel.

The Contractor shall have responsibility for submittal and distribution of shop drawings. The provisions of Section 2, Drawings, of the New York State Steel Construction Manual will apply, except as modified herein or by other notes in the Contract documents.

The submittal shall consist of the following phases:

**Art Approvals:** Final scaled color laser comp of each sign panel prior to production.

**Color Approval:** Custom colors to match specified. Provide lab sample for color approval.

The attached Shop Drawing Submittal Procedure supersedes the shop drawing submittal and distribution requirements of any and all sections of the New York State Steel Construction Manual.

### **MATERIALS**

**Panel:** The exterior grade (folia/phenolic resin or similar process), UV and graffiti proof weather resistant Interpretive Exhibit Panel is self supporting and does not require bonding to a supportive substrate. Panels shall be as designed, manufactured and supplied by (or approved equal):

Folia Industries  
58 York Street  
Huntington, Quebec, Canada J0S1H0  
(888) 264-6122

Empact Exhibits  
Corpus Christi, Texas 78404  
(361) 241-3405

Grand Visuals  
2300 West 2<sup>nd</sup> Avenue  
Denver, Colorado 80223  
(877) 221-3860

**Copy:** Digital file with images, fonts and final art work shall be provided to the Engineer for submittal to the manufacturer for panel fabrication. Digital file is to be fused into a single panel with phenolic resin. The graphics and resins are fused under the effect of high temperature and pressure.

Panel layout, colors and fonts shall be approved by the Engineer prior to production.

**ITEM 01615.1004 - INTERPRETIVE EXHIBIT PANEL**

**Panel Color:** Four colors as approved by the Engineer and half-tones for prints of black and white photographs.

**Panel Thickness:** Minimum 1/2 inch.

**Deliverables:** One exterior grade folia panel for each Interpretive Panel.

**CONSTRUCTION DETAILS**

Panel shall be installed on the kiosk structure as recommended by the manufacturer and approved by the Engineer.

**METHOD OF MEASUREMENT**

Interpretive Exhibit Panels shall be measured by the number of panels as specified on the contract documents acceptably placed by Contractor and approved by the Engineer.

**BASIS OF PAYMENT**

The unit price bid per panel shall include the cost of all labor, materials and equipment necessary to design, manufacture and deliver the work.

***Payment will be made under:***

<b>Item No.</b>	<b>Item</b>	<b>Pay Unit</b>
01615.1004 M	Interpretive Exhibit Panel	Each

DISAPPROVED BY EIT 12-001