

**ITEM 615.1010NN07 - INTERPRETIVE SIGN MOUNTING STRUCTURE**

**DESCRIPTION**

This work shall consist of furnishing and installing an Interpretive Sign Mounting Structure in accordance with the contract documents and as directed by the Engineer.

**MATERIALS**

**Lumber:**

Posts, Beams, Rafters, Stringers, Braces, Planks, Fascia, Trim	Pressure treated as per Section 708-31 Southern Yellow Pine #2 construction grade or better
---	---

**Metal Fasteners:**

Carriage Bolts, Washers, Nuts, Common Nails, Wood Screws, etc.	Hot dipped galvanized, stainless steel or otherwise compatible with ACQ pressure treated lumber. Carriage Bolts shall be grade 5 steel or greater.
---	--

**Roofing Materials**

Roofing Shingles	Asphalt roofing shingles as specified in plans
------------------	--

Roofing Paper	Asphalt roofing felt paper
---------------	----------------------------

Drip Edge	Aluminum
-----------	----------

**Other Materials**

Concrete	Shall meet requirements for 555.0104 Footing Concrete, Class A
----------	---

Steel Frame	Shall meet requirements of ASTM A-709
-------------	---------------------------------------

Paint	Shall meet requirements of Section 740-02 Painting Timber and Lumber Color shall be as specified in plans &/or details
-------	--

**CONSTRUCTION DETAILS**

Interpretive Sign Mounting Structure shall be constructed as specified in the contract plans.

Construction and connections of materials to be made in craftsman like manner following accepted practices of the carpentry trade.

**Footings:**

Postholes shall be dug, augured or core drilled to form plumb, straight sides as per the dimensions shown on the plans.

**Posts:**

Posts shall be centered on/within the concrete footings and plumbed as per specifications.

**ITEM 615.1010NN07 - INTERPRETIVE SIGN MOUNTING STRUCTURE**

**METHOD OF MEASUREMENT**

This work will be measured as the number of Interpretive Sign Mounting Structure satisfactorily furnished and installed.

**BASIS OF PAYMENT**

The unit price bid shall include the cost of furnishing all labor, materials, and equipment necessary to satisfactorily complete the work.

Note: NN denotes serialized pay item if multiple units of different styles or sizes are used.

DISAPPROVED BY EI 12-001