

ITEM 08615.1012 M - INTERPRETIVE PANEL INSTALLATION

DESCRIPTION:

This work shall consist of furnishing and installing a Steel Pedestal Stand for an Interpretive Panel as shown on plans.

MATERIALS:

Steel Hardware

Steel Plates and shall meet the requirements of ASTM A-709.

Steel Posts and shall meet the requirements of ASTM A-709.

Steel Anchor Plates and shall meet the requirements of ASTM A-709.

Steel Anchor Bolts and Nuts shall meet the requirements of ASTM A-325.

Paint

All primer and finish coats of paint used on this contract shall be produced by the same manufacturer and selected from the Department's Approved List for moisture-curing urethane paint systems

The primer and finish coat shall be of the color as specified in the Contract Documents.

Interpretive Panel

Interpretive Panel will be provided by New York State Department of Parks, Recreation and Historic Preservation.

CONSTRUCTION DETAILS:

Posts shall be set plum and shall be welded to steel plate and steel anchor plate as shown on plans. Steel Plate shall have pre-drilled holes for security screws which will align with the existing pre-drilled holes on the Interpretive Panel. Anchor plate shall have pre-drilled holes for Anchor Bolts and Nuts. Anchor bolts shall be cast-in place. Contractor has the option of using epoxy drilled inserts. Expansion anchors are prohibited. Sign Panel shall be connected to Steel Plate with security screws. Each steel post shall have one 8mm weep hole drilled at its base as indicated on plans.

The contractor shall submit finish coat paint samples to the Engineer for approval. Paint samples shall be submitted at least ten working days prior to the date of installation.

ITEM 08615.1012 M - INTERPRETIVE PANEL INSTALLATION

METHOD OF MEASUREMENT:

The work will be measured as the actual number of interpretive panels installed as per these specifications.

BASIS OF PAYMENT:

The unit price bid per interpretive panel shall include the cost of furnishing all labor, equipment and materials necessary to satisfactorily complete the work.