

**ITEM 08615.1013xxx M - INTERPRETIVE SIGN INSTALLATION**

**DESCRIPTION:**

This work shall consist of installing a wood post and mounting of an Interpretive Sign, provided by others.

**MATERIALS:**

Steel Hardware (as shown on standard sheets)

Stainless steel connecting products 715-16.

Stiffeners & miscellaneous hardware 730-22.

Post

Covered separately under Item 15645.1702.

Interpretive Panel

Interpretive Sign will be provided by New York State Department of Transportation.

**CONSTRUCTION DETAILS:**

Installation shall be in accordance with Class 1 ground mounted sign panel. Installation shall be as shown in the Standard Sheets and Standard Specifications with the addition of the following:

Posts shall be set plum.

Post shall be drilled and treated for location of security screws (bolts spot welded to nut)

Interpretive Sign shall be connected to stiffeners with security screws.

Interpretive Sign shall be mounted to Post using security screws.

**METHOD OF MEASUREMENT:**

The work will be measured as the actual number of Interpretive Signs installed as per these specifications.

**BASIS OF PAYMENT:**

The unit price bid per interpretive panel shall include the cost of furnishing all labor, equipment and mounting hardware necessary to satisfactorily install each sign.

**ITEM 08615.1013xxx M - INTERPRETIVE SIGN INSTALLATION**

DISAPPROVED BY EI 12-001